



**बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०**  
**BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.**  
**(A Govt. of Bihar Undertaking)**

ISO 9001; 14001; OHSAS 18001  
Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna-800004  
Tel. No.: 0612-2660850 • Fax No.: 0612-2660256  
E-mail: [bseidc@gmail.com](mailto:bseidc@gmail.com) • website: <http://www.bseidc.in> • CIN U80301BR2010SGC015859

**दर आमंत्रण हेतु अल्पकालीन कोटेशन आमंत्रण सूचना संख्या-08 वर्ष-2020-21**

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि० पटना के निबंधित संवेदकों/ख्याति प्राप्त फर्मों/कंपनियों से दिनांक:- **26.06.2020** के अपराहन 03:00 बजे तक राज्य के विभिन्न जिलान्तर्गत विभिन्न निर्माण कार्यो में प्रयोग हेतु Fire Fighting से संबंधित कार्यो हेतु गैर अनुसूचित मदों की आपूर्ति एवं अधिष्ठापन के लिए निम्नांकित मदों हेतु मुहरबंद कोटेशन अधीक्षण अभियंता, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०, पटना के कार्यालय में प्राप्त किया जाएगा एवं उसी दिन अपराहन 03:30 बजे कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष खोला जाएगा।

Sl. No.	Description of items	Qty	Unit	Rate In Digits	Rate In Words
1	Providing, storing, handling, shifting, installation, testing and commissioning of portable fire Extinguishers as described below: 4 kg carbon dioxide extinguisher, IS marked, with high pressure discharge tube, horn, control valve, CCE approved cylinder of Make :- ABC/Eco Fire all complete job as per direction of E/I.	1	Each		
2	Providing, storing, handling, shifting, installation, testing and commissioning of portable fire Extinguishers as described below: 5 kg carbon dioxide extinguisher, IS marked, with high pressure discharge tube, horn, control valve, CCE approved cylinder of Make :- ABC/Eco Fire all complete job as per direction of E/I.	1	Each		
3	Supply, installation and fixing of M.S bucket of 9 liters capacity painted with red oxide paint & lettered as 'Fire' with White and red mounted on freestanding stand, as required including filling with dry sand all complete job as per direction of E/I.	1	Each		
4	Supply, installation and fixing of First aid box as approved by St.John Ambulance Brigade /Indian Red Cross society conforming to IS : 2217 - 1963 all complete job as per direction of E/I.	1	Each		
5	Supply, installation and fixing of MS Axe of approved by St.John Ambulance Brigade /Indian Red Cross society conforming to IS : 2217 - 1963 all complete job as per direction of E/I.	1	Each		

*Handwritten signature/initials*

6	Supply, installation and fixing of Shock treatment chart duly mounted on a wooden frame with glass on, as required in 2 languages (Hindi & English) all complete job as per direction of E/I.	1	Each		
7	Doors and frame Supply, installation and fixing of MS door frame 1200x2100 door capable of accommodating fire hose reel, landing valve, hose pipes, fittings & accessories. The door shall have a front glass with lock and key arrangement & shall be painted with post office red colour (approval shall be taken on the basis of submitted sample before ordering) Cost of fire extinguishers not included in item rate. (Liasioing with civil contractor for making 1200x600x2100 Recessed type mansoary box all complete job as per direction of E/I.	1	Each		
8	Supply, installation and fixing of M.S. fire hose cabinet (750x600x250mm) made out of 16 gauge M.S. sheet capable of accommodating landing valve, hose pipes, fittings & accessories. The box shall have a front glass door with lock and key arrangement & shall be painted with post office red colour (approval shall be taken on the basis of submitted sample before ordering) - for external and roof hydrant all complete job as per direction of E/I.	1	Each		
9	Providing and fixing of self illuminated / auto glow "EXIT" signs printed on photoluminescent sheet containing self illuminated base chemical, of appropriate size not less than 400 x 150 mm, suspended from ceiling or fixed to the walls with accessories as required all complete job as per direction of E/I.	1	Each		
10	Supply, installation and fixing of optical/Photoelectric type smoke detectors of photo-optic sensing chamber, 12/24 volt D.C., twin visual alarm indicator "Blink" in stand by and "Steady" in alarm (LED's) complete in all respects with base as required all complete job as per direction of E/I.	1	Each		
11	Providing, fixing, testing and commissioning of manual call points (Addressable type resetable manual call point) break glass type housed in sheet steel / Polymer housing in surface/recess including making connections with wires complete in all respects and as per specifications. The manual call point should have an indicator, which should "blink" in stand by condition all complete job as per direction of E/I.	1	Each		
12	Providing, fixing, testing and commissioning of electronic hooters housed in sheet steel / Polymer housing suitable for wall / ceiling and surface / recess mounting including making connections with wires complete in all respects and as per specifications all complete job as per direction of E/I.	1	Each		


*Rajesh*

*81*

13	Supply , installation , testing and commissioning of fire control module all complete job as per direction of E/I.	1	Each		
14	Providing, fixing, testing and commissioning of fire alarm main control and indicating panel, Addressable microprocessor based to monitor all local/zonal control panels on each floor or directly detectors as per the case, pulser, timer for dual stage alarm facility complete with indicators, floor selector switches, stand by SMF battery, battery charger, battery box, connections to building automation system / Fire fighting pump panel etc.The panel shall have facility of automatic dialling to 5 telephone numbers in case of alarm. The main control panel should give a distinct visual signal of the isolation of loop from the local indication panel. If all the loops at the local panel are isolated or if the fuse of the LCP gets blown, it should result in an open circuit fault indication at the Main Panel. Each loop should have provision of activation of hooter all complete job as per direction of E/I. 2-Loops main control panel	1	Each		
15	Providing, installing, testing and commissioning of repeater panel suitable for common fire / fault indication of 5 nos main Fire Alarm panels with sounder, stand by SMF battery, battery charger, battery box, LCD alpha numeric character display with accept / reset buttons for alarm. The panel shall be connected to the main fire alarm panel all complete job as per direction of E/I.	1	Each		

### विशेष शर्तें-

- यह कोटेशन सिर्फ दर निर्धारण हेतु आमंत्रित किया गया है।
- कोटेशनदाताओं को अपना दर (सभी करों, GST एवं दुलाई व्यय के साथ) अंक एवं अक्षरों में उद्धृत करना होगा।
- विशेष सूचना के लिए सूचनापट्ट या वेबसाइट [www.prdbihar.gov.in](http://www.prdbihar.gov.in) एवं [www.bseidc.in](http://www.bseidc.in) देखें अथवा अधोहस्ताक्षरी के कार्यालय में कार्यावधि में संपर्क किया जा सकता है।

  
 13/5/2020  
 अधीक्षण अभियंता  
 BSEIDC, पटना।

