



बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०

BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

(A Govt. of Bihar Undertaking)

ISO 9001; 14001; OHSAS 18001

Shiksha Bhawan, Bihar Rashtrabhasha Parishad Campus, Acharya Shivpujan Sahay Path, Saidpur, Patna-800004

Tel. No.: 0612-2660850 • Fax No.: 0612-2660256

E-mail: bseidc@gmail.com • website: <http://www.bseidc.in> • CIN U80301BR2010SGC015859

दर आमंत्रण हेतु अल्पकालीन कोटेशन आमंत्रण सूचना संख्या-20 वर्ष-2020-21

बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि० पटना के निबंधित संवेदकों/ख्याति प्राप्त फर्मों/कंपनियों से दिनांक:- 22.09.2020 के अपराहन 03:00 बजे तक राज्य के विभिन्न जिलान्तर्गत विभिन्न निर्माण कार्यों में प्रयोग हेतु IT Products से संबंधित कार्यों हेतु गैर अनुसूचित मदों की आपूर्ति एवं अधिष्ठापन के लिए निम्नांकित मदों हेतु मुहरबंद कोटेशन अधीक्षण अभियंता, बिहार राज्य शैक्षणिक आधारभूत संरचना विकास निगम लि०, पटना के कार्यालय में प्राप्त किया जाएगा एवं उसी दिन अपराहन 03:30 बजे कोटेशनदाताओं या उनके अधिकृत प्रतिनिधियों के समक्ष खोला जाएगा।

Sl. No.	Description of items	Qty	Unit	Rate In Digits	Rate In Words
1	Supplying,Installing,Testing with Dome Camera Form factor 2 Megapixel high resolution Usage Indoor Usage Lens 1/3" angle of view: Day /night IR as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make Secure eye, Hikvision or CP Plus.	1.00	Each		
2	Supplying,Installing,Testing with bullet Camera Form factor 2 Megapixel high resolution Usage Indoor Usage Lens 1/3" angle of view: Day /night IR as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make Secure eye, Hikvision or CP Plus.	1.00	Each		
3	Supplying,Installing,Testing Network Video Recorder with 32 Channel Video compression H-265 Channel 16 System Resolution multi-channel real time recording, playback, network operation Preview 1/4/8/16 Display Quality VGA, HDMI, Backup Mode Network/ USB Device Interface port 1 x HDMI,1 x SATA (Single maximum support 6TB each) 12V/4A as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Pelco, Honeywell, Sony, Bosch, Hikvision or similar	1.00	Each		

10

4	<p>Supplying,Installing,Testing 32 Port POE GIGABIT Network Switch with Gigabit Copper Ports- At least 24 Nos.of 10/100/1000 base T ports with RJ 45 Connector Gigabit Fiber Uplink Ports (1G/10G) -At Least 4 Nos of 1G SFP Ports, Port Status Display- Each Port must have a dedicated led for status display, IP Multicast - IGMP Snooping, In-band Management -Web based management (On https/http)-SSH based management (SSH v2). Telnet Out-of-band Management -Console Port -Management Ethernet Port. Interface cables - Console cable and power cable (As per Indian standards) to be provided. Make HP, Cisco, Net gear, D-Link, Hikvision Juniper or similar.</p>	1.00	Each		
5	<p>Supplying,Installing,Testing Hard Disk with Storage Capacity -6 TB, HDD Type -Surveillance, Make- Seagate, WD , samsung.</p>	1.00	Each		
6	<p>Supplying Cat 6E UTP Cable with Network cable - 23 AWG Solid Bare Copper with Polyolefin Tape, Tight lay system with Table 2 Colour coding, Short-staggered pair, Non-led FR PVC, Flexible separator, optimum pair to pair & power sum cross talk, as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make D-Link, Molex, Digi link or similar all complete job including VC casing and capping.</p>	1.00	Meter		
7	<p>Supplying,Installing,Testing Mount Network Rack Enclosure with Accessories Specification Racks manufactured out of steel punched, formed and powder coated. Racks should be manufactured by ISO 9001-2008 Certified Company. Racks should have Front Toughened Glass Door with lock & Key. Rack should have ventilations slots on the both sides Rack Should have provision for cable entry Exit from top & Bottom with rubber grommets. as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make: VALRACK/D-LINK/Net Rack</p>	1.00	Each		
8	<p>Supplying,Installing,Testing Display Panel with Screen Size- 32-inch Aspect Ratio- 16:9 Panel Backlight -IPS/Direct-LED Backlight Scanning - 100Hz Resolution -1920 X 1080 pixels Viewing Angle-178 X 178 VIDEO IN -RCA X 1 AUDIO IN (L/R)/PC AUDIO IN -RCA Pin Type X 2 HDMI IN- TYPE A Connectors X 2 COMPONENT IN- Y, PB/CB, PR/CRX1 USB Input -USB 2.0 X 1 as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I (Make:- Samsung/Sony/LG/Panasonic)</p>	1.00	Each		

(Handwritten mark)

9	<p>Supplying,Installing,Testing 1 KVA UPS with Some specification i)1 KVA/600W UPS ii)Input Voltage Range - 140-300V AC iii) Input Frequency - 50 Hz iv) Output Voltage - 230V AC v) Cord Length :1.5 mtr (min) vi) Maintenance-free sealed ,leakproof Battery vii) Full Protection - Discharge, overcharge, and overload protection viii) Auto restart while AC recovery ix) ROHS Complied x) Power backup of minimum 30 minutes for camera and network switch & as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. (Make:- Microtek/Exide/V-Guard)</p>	1.00	Each		
10	<p>Providing fitting and fixing of ahuja make of AMPLIFIER 125WATTS USB as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I.</p>	1.00	Each		
11	<p>Supplying,Installing,Testing and Commisioning of Multi 111-8-CH Splitter/Mixer as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make- DIBox studio master or ahuja</p>	1.00	Each		
12	<p>Supplying,Installing,Testing and Commisioning of SMX 302T WALL/ceiling SPEAKER (12 watt) as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make- F&D/ahuja.</p>	1.00	Each		
13	<p>Supplying,Installing,Testing and Commisioning of AWM 700 U2 CORDLESS MIC as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make:-Studio Master/ahuja.</p>	1.00	Each		
14	<p>Supplying,Installing,Testing and Commisioning of 6U Rack as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I.Make: VALRACK/D-LINK/Net Rack</p>	1.00	Each		
15	<p>Supplying & Installing of speaker cable Wire as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I</p>	1.00	meter		
16	<p>Supplying,Installing,Testing and Commisioning of 5Kva Stabilizer as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make- V-Guard/Servo</p>	1.00	Each		

2


17	Providing fitting and fixing of ahuja or equivalent make of HOST CONTROL UNIT (CWS-8300 R) as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make:-Ahuja/StudioMaster	1.00	Each		
18	Supplying & Fixing wired mike with stand as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I make-ahuja/F&D.	1.00	Each		
19	Supplying, Installing, Testing & Commissioning of Desktop Computer with Intel core i3 9th Gen with 4GB DDR4 Ram, 1TB Hard disk (WIFI/BT) USB Keyboard, USB Mouse, Preofessional Win10, 18.5" TFT having 3 Years Onsite warranty as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I (Make-DELL/ACER/LENOVO/HP)	1.00	Each		
20	Supplying, Installing, Testing & Commissioning of Desktop Computer with Intel core 8th Generation Intel® Core™ i7 processor, 8 GB RAM, 2 TB HDD storage, (WIFI/BT), 256 GB SSD storage USB Keyboard, USB Mouse, Professional Win10, 18.5" TFT having 3 Years Onsite warranty as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I (Make-DELL/ACER/LENOVO/HP)	1.00	Each		
21	OnLine UPS Supplying, Installing, Testing & Commissioning of On Line UPS of capacity 40 KVA, Nominal Input voltage: 135-300V AC / 50Hz+5% Output Voltage : 230V VA + 9%, 1hour Power backup, one year warranty with Battery for online UPS with Rack & links making all connection as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make:- (APC/microtek/luminous)	1.00	Each		
22	Supplying, Installing, Testing & Commissioning of A4 Mono Monolithic printer with Print speed black: Print Speed (A4): Up to 27ppm, Recommended monthly print volume: 500 - 2,500 pages, Print Resolution: Up to 1200 x 1200dpi (equivalent), FPOT (A4): 6.0secs. as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I (make-Canon/HP/Epson)	1.00	Each		
23	Networking for a computer including patch cable, Mounting plate with GI box & patch cord and all other required fittings as per technical specifications including carriage all complete job as per direction of E/I	1.00	Each		

21

24	Supplying, Installing, Testing & Commissioning of Server- Processor 4U/Intel Xeon E-2104G (3.2GHz/4core/8mb/65w)/ RAM 16GB Turbo DDR4, HDD 1TB/NIC 3x1 Gig Port 3 Year Onsite Warranty, Keyboard And Mouse, Monitor 20" LED as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make-LG/Samsung/Sony	1.00	Each		
25	Supplying, Installing, Testing & Commissioning of Licence- Microsoft Windows Server 2016 Std Edition License as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I	1.00	Each		
26	Providing fitting and fixing podium with Inbuilt Speakers, Amplifier, Cordless Mic, Podium Mic, Usb Port as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I. Make-Ahuja	1.00	Each		
27	RJ-45 Connector for termination of 4 pair termination CAT-6 Cable as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I	1.00	Each		
28	HDMI to HDMI cable of 3 meter length as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I	1.00	Each		
29	Supply and Erecting modular type computer jack RJ 45 with mounting plate and box with wiring connections complete of as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make :- Dlink/ Legrand.	1.00	Each		
30	Supplying, installation, testing and commissioning of 5kVA online UPS System with 30 minutes back up including batteries, interconnecting cables, battery racks as per technical specifications including carriage and necessary required equipment all complete job as per direction of E/I Make:-(APC/microtek/luminous)	1.00	Each		

विशेष शर्तें—

- यह कोटेशन सिर्फ दर निर्धारण हेतु आमंत्रित किया गया है।
- कोटेशनदाताओं को अपना दर (सभी करों, GST एवं ढुलाई व्यय के साथ) अंक एवं अक्षरों में उद्धृत करना होगा।
- विशेष सूचना के लिए सूचनापट्ट या वेबसाइट www.prdbihar.gov.in एवं www.bseidc.in देखें अथवा अधोहस्ताक्षरी के कार्यालय में कार्यावधि में संपर्क किया जा सकता है।


 14/9/2020
 अधीक्षण अभियंता
 BSEIDC, पटना।