

अहार BIHAR

10444 28-11 1000 AC 325063

AC 325063

THE HOLD STORM STORMS THE WAY

- STORM TO THE HOLD STORMS THE WAY

- STORM TO THE HOLD STORMS THE WAY

- WANTED TO THE MEAN THE PROPERTY THE WAY

- WANTED TO THE MEAN TO THE WAY

- WANTED TO THE MEAN THE MEAN THE WAY

- WANTED TO THE MEAN THE MEAN THE WAY

- WANTED TO THE MEAN THE WAY

- WANTED TO THE MEAN THE WAY

- WANTED TO THE WAY

- WANTED T

SUPPLEMENTARY AGREEMENT No. 129 SBD of 2018-19 of Original Agreement No. 311 SBD of 2015-16

Name of Work

: Construction of Aryabhatta Knowledge University at Mithapur, Patna" in the State of Bihar

Supplementary
Agreement for the Work

: Additional Work of Internal Raod, Tubewell, Drain, Platform, Boundary Wall and other work etc.

Name of Agency

Dipanshu Promoter & Builder Pvt. Ltd.

This agreement, made the 29th November., 2018 between Bihar State Educational Infrastructure Development Corporation Ltd. Patna. Hereinafter called the Employer of the first part and Dipanshu Promoter & Builder Pvt. Ltd., 2 B, Vatika Apartment, Line Tank Road, Ranchi-834001, Jharkhand hereinafter called "the Contractor of the other part".

Whereas the Employer's is desirous that the Contractor execute the extra items (Additional Work of Internal Raod, Tubewell, Drain, Platform, Boundary Wall and other work etc. in the Campus of Aryabhatt Knowledge University, Mithapur, Patna) for the work of "Construction of Aryabhatta Knowledge University at Mithapur, Patna" in the State of Bihar hereinafter called "the work" and the Employer has accepted the Bid by the Contractor for the execution of such work and the remedying of any defects therein, at a cost of Rs. 5,38,34,769/- (Rupees Five Crore Thirty Eight Lac Thirty Four Thousand Seven Hundred Sixty Nine only)

For Diparishu Promoter and Builder Pvt. Ltd.

Sama Sind

Managing Director

29.11.2018

Chief Engineer

8.3.E.I.D.C. Ltd, Patna

Viggini' A. Company

Performance Security

Name of Agency:- '' Dipanshu Promotors& Builders Pvt. Ltd."

Performance Security of Regarding regarding 'AKU Supplimentary Agreement

BG No.

<u>Period</u>

<u>AMOUNT</u>

4401IFIBG180026

26.11.18 to 25.11.20

12,50,000.00

Total-

12,50,000.00

(Rupees Twelve Lac Fifty Thousand only)

For Dipanshu Promoter and Builder Pvt. Ltd.

Samon 3 mh.

Managing Director.

Amir Xv. Son 29/11/18
विकास सम्मितिकारी
विकास सम्मितिकारी

Chief Eng neer B.S.E.I.D.C. Lkd, Patna

		•	
			-
			A CONTRACTOR OF THE PARTY OF TH
			~)
			· / /
			;- - }
			, problem
			À
	•		3000
			. 1
			t Jan
)
			7 700
			, postar,
		£	, 60m,
			× 10 mg
)-18hp
)
			_)
			100 mg/m
			, Alleria
			J.
			J.
) 1
			#



ideit Bihar

Dinesh Kr. Gupta Stamp Vender, Civil Cour Patria N 51/87

Name of Work

AGREEMENT No. 311 SBD of 2015-16

"Construction of Aryabhatta Knowledge University at Mithapur, Patna" in the State of Bihar

Part-B @ Item rate Basis)

Name of Agency Date of Commencement

Dipanshu Promoter & Builder Pvt. Ltd. 08-09-2015.

Time of completion

Twenty Four Months

Estimate Cost Agreement V lue

Rs 93,61,63,139/- (Part-A + Part-B) Rs. 99,04,53,584/- (Part-A @ 2.45% above BOQ rates &

Earnest Mone Performance Security

Rs. 1,98,10,000/- (Details attached)

This preement, made the OSm September., 2015 between Bihar State Educational Infrastructure Development Corporation Ltd. Patna. Hereinafter called the Employer of the first part and Dipanshu Promoter & Builder Pvt. Ltd., 2 B, Vatika Apartment, Line Tank Road, Ranchi-834001, Jharkhand hereinafter called "the Contractor of the other part".

Whereas the Employer's is desirous that the Contractor execute "Construction of Aryabhatta Knowledge University at Mithapur, Patna" in the State of Bihar hereinafter called "the work" and the Employer has accepted the Bid by the Contractor for the execution of such work and the remeding of any defects therein, at a cost of Rs. 99,04,53,584/- (Rupees Ninety Nine Crore Four Lacs Fifty Three Thousand Five Hundred Eighty Four Only.)

For Dipansh Promoter and Builder Pvt. Ltd.

anjan sinh. **Managing Director**

Managing Director

Chief Engineer B.S.E.I.D.C. Ltd. Palne C. Ltd. Patna

4000

Ŋ

BIHAR STATE EDUCATIONAL INFRASTRUCTURE DEVELOPMENT CORPORATION LTD.

Supplementary BOQ for Constrution of Aryabhatta Knowledge University at Mithapur, Patna

SL.	SOR No.	rame of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
1	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintel	3,804.02	588,00	Rupees Five Hundred Eighty Eight Only
2	AR	Additional cost for use of plasticizers in RCC work above plinth level.	cum	13,319,38	98.10	Rupees Ninety Eight and Ten Paisas Only
3	20.6.1.	Vertical load testing of piles in accordance with IS 2911 (Part IV) including installation of loading platform and preparation of pile head or construction of test cap and dismantling of test cap after test etc. complete as per specification & the direction of Engineer in-charge. Single pile upto 50 tonne capacity. Routine test	per test	41.00	18,889.80	Rupees Eighteen Thousand Eight Hundred Eighty Nine and Eighty Paisas Only
4	13.46A .1	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coat applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior	Sqm	22,051.82	81,70	Rupees Eighty One and Seventy Paisas Only
5	13.80A	Providing and applying white cement based putty of average thickness 2 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	142,284.09	118.70	Rupees One Hundred Eighteen and Seventy Paisas Only
6	0.12	Extra for providing frosted glass panes 4 mm thick instead of ordinary float glass panes 4 mm thick in doors, windows and elerestory window shutters. (Area of opening for glass panes excluding portion nside rebate shall be measured)	sqm	500.00	6.30	Rupees Six and Thirty Paisas Only

For Dipanshu Promotor and Suspan Per Sun.

Managing Director

Chief Engineer B.S.E.I.D.C. Ltd, Patna

SL.	SOR No.	Name of Rems	Unit	Quantity	Rate (in digits)	Rate (In Words)
7	9.61.1.	Providing and fixing wooden molded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete 2nd class teak wood 50x20mm	ı	4,887.05	138.40	Rupees One Hundred Thirty Eight and Forty Paisas Only
8	9.7.8	Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia wire and 1.4 mm wide aperture with	Sqm	989.37	1,513.10	Rupees One Thousand Five Hundred Thirteen and Ten Paisas Only
9	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering all work upto plinth level.				Only
	4.1.6	1:3:6 (1 Cement; 3 coarse sand :6 graded stone aggregate 40 mm nominal size)	Cum	42.68	2,640.90	Rupees Two Thousand Six Hundred Forty and Ninety Paisas
10	8.10.2	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade	Each	44.63	3,263.50	Rupees Three Thousand Two Hundred Sixty Three and Fifty Paisas Only





.

tA
7
J

SL.	SOR No.	Name of Rems	Unit	Quantity	Rate (in digits)	Rate (In Words)
11	20.2	Boring, providing and installing bored cast in-situ reinforced cement concrete piles of grade M-25 of specified diameter and length below the pile cap, to carry a safe working load not less than pecified excluding the cost of steel reinforcement but including the cost of boring, with bentonite solution and temporary casing of appropriate length for setting out and removal of same and the length of the pile to be embedded in the pile cap etc. all complete, including removal of excavated earth with all lifts and leads (Length of pile for payment shall be measured upto bottom of pile cap).	of d e t t f f			
	20.2.1	300 mm dia piles	metre	816.00	1,309.30	Rupees One Thousand Three Hundred Nine an Thirty Paisas Only
12		carriage of Earth	Cum	17,917.75	277.04	Rupees Two Hundred Seventy Seven and Four Paisas Only
13			,Cum	24.78	1,119.48	Rupees One Thousand One Hundred Ninetee and Forty Eight Paisas Only
14	RCD 4.12	Wet Mix Macadam (Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.) With Vibratory Roller		536.87	975.00	Rupees Nine Hundred Seventy Five Only
15	RCD s 5.1 c r	Prime coat (Providing and applying primer coat with bitumen emulsion on prepared surface of granular Base including clearing of road surface and spraying primer at the ate of 0.60 kg/sqm using mechanical neans.)	Sqm	3,808.70	34.80	Rupees Thirty Four and Eighty Paisas Only

For Dipanshu Promoter and Builder Pvt. Ltd.

Sampy Smanaging Director

Chief Eng neer

3.S.E.I.D.C. Ltd, Patna

.

		Supplementary BOQ for Constitution of Aryapha	T	wicage onivers	T T T T T T T T T T T T T T T T T T T	Patna 💍
SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
16	RCD 5.2	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom	j	7,617.39	9 12.50	Rupees Twelve and Fifty Paisas Only
17	RCD 5.3A (ii)	Bituminous Macadam (Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction) for GradingII (19 mm nominal size)		190,43	7,022.00	Rupees Seven Thousand Twenty Two Only
18	RCD 5.7A (II)	Semi - Dense Bituminous Concrete (Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder @ 4.5 to 5 % of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem collers to achieve the desired compaction as per MoRTH specification clause No. 508 complete in all respects)	Cum	95,22	9,800.00	Rupees Nine Thousand Eight Hundred Only
19	RCD 8.13 iii g	for Grading II(10 mm nominal size) Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface (Providing and laying of hot pplied thermoplastic compound 2.5 mm hick Including reflectorising glass beads @ 250 Ims per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as er IRC:35 .The finished surface to be evel, uniform and free from treaks and holes.)	Sqm	83.00	812.00	Rupees Eight Hundred Twelve Only

For Diparishu Promoter and Bunder Pvc. Cto.

Managing Director.

Chief Eng neer

3.S.E.I.D.C. Ltd, Patna

	١
フ	,

SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
20	14.6	Renewing glass, with wooden fillets wherever necessary				
	14.6.2	Float glass panes weighing 10kg/m2 (4mm thick)	sqm	289.10	705.80	Rupees Seven Hundred Five and Eighty Paisas Only
21		Providing corrugated G.S. sheet roofing fixed with G.I.J. or hooks, bolts and nuts 8 mm diameter with bitumen and G. I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on over lapping of sheets complete (upto a pitch of 60°) excluding the cost or purlins, rafters and trusses. 0.63 mm thick with zinc coating not less than 275 gm/m2	Sqm	381.69	700.70	Rupees Seven Hundred and Seventy Paisas Only
22	12.1.5	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with G.I.J. or L hooks Bolts and nuts 8 mm dia. G. 1. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m2	mtr.	21.20	429.00	Rupees Four Hundred Twenty Nine Only

For Dipanshu Promoter and Builder Pvt. Ltd.

Chief Engineer
B.S.E.I.D.C. Ltd, Patna

. . .

SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
23	12.1.5	Providing, assembling and supplying vision glass panels (IGUs) comprising of hermetically-sealed 6-12- 6 mm insulated glass (double glazed) vision panel units of size and shape as required and specified, comprising of an outer heat strengthened float glass 6mm thick, of approved colour and shade with reflective soft coating on surface # 2 of approved colour and shade, an inner Heat strengthned clear float glass 6mm thick, spacer tube 12mm wide, dessicants, including primary seal and secondary seal (structural silicone sealant) etc. all complete for the required performances, as per the Architectural drawings, as specified and as directed by the Engineer-inCharge. The IGUs shall be assembled in the factory/ workshop of the glass processor. (Payment for fixing of IGU Panels in the curtain glazing is included in cost of item No.26.2)For payment, only the actual area of glass on face # 1 of the glass panels (excluding the areas of the orgoves and weather silicone	Sqm	165.60	4,279.50	Rupees Four Thousand Two Hundred Seventy Nine and Fifty Paisas Only
24	17.25	Providing and fixing white vitreous china wash basin including making all connections but excluding the cost of fittings:				
	17.25.1	wash basin of size 630x450 mm	Each	373.00	1,084.20	Rupees One Thousand Eighty Four and Twenty Paisas Only
25	17.1	Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm sand cast Iron P or S trap, 10 litre low fixtures complete, including cutting and making good the walls andlevel white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and floors wherever required:				

For Dipanshu Promoter and Builder Pvt. Ltd.

Managing Director



SL.	SOR No.	Traine of Rems	Unit	Quantity .	Rate (In digits)	Rate (In Words)
	17.1.1	White Vitreous china Orissa pattern W.C pan of size 580x440 mm with integral type foot rests	Each	13.00	3,035.40	Rupees Three Thousand Thirty Five and Forty Paisas Only
26		Providing and fixing Chlorinated Polyviny Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making the wall good 15 mm nominal outer dia pipes				Rupees Two
	18.8.1		Mtr.	450.00	241.00	Hundred Forty
		20 mm nominal outer dia pipes				One Only Rupees Two
	18.8.2	K-F	Mtr.	2,781.22	269.60	Hundred Sixty Nine and Sixty
27	18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement ,trenching ,refilling & testing of joints complete as per direction of Engineer in Charge.				Paisas Only
	18.9.3	25 mm dia, nominal dia pipe	Mtr.	786.95	193.80	Rupees One Hundred Ninety Three and Eighty
	18.9.4	32 mm dia, nominal dia pipe	Mtr.	328.90	251.10	Paisas Only Rupees Two Hundred Fifty One and Ten Paisas Only
	18.9.5	0 mm dia, nominal dia pipe	Mtr.	413.10	344.00	Rupees Three Hundred Forty Four Only

For Dipanshu Promoter and Builder Pvt. Ltd.

Samuel Managing Director

Chief Eng neer

S.S.E.I.D.C. Ltd, Patna

Ì J 191

		The second of th	<u> </u>		*	
SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
	18.9.6	50 mm dia, nominal dia pipe	Mtr.	1,400.06	532.30	Rupees Five Hundred Thirty Two and Thirty Paisas Only
	18,9.7	62.50 mm dia, nominal dia pipe	Mtr.	210.50	1,540,70	Rupees One Thousand Five
	18.9.8	75 mm dia, nominal dia pipe	Mtr.	45.20	2,179.20	Rupees Two Thousand One
W	18.9.9	100 mm dia, nominal dia pipe	Mtr.	18.00	3,014.30	Rupees Three Thousand
28	12.79.3	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. Single tee with door 110x110x110mm		314.00	315.90	Rupees Three Hundred Fifteen and Ninety Paisas Only
29	12.79.6 .2	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. Shoe plain 110mm shoe		92.00	314.73	Rupees Three Hundred Fourteen and Seventy Three Paisas Only

For Dipanshu Promotor and Builder Pvt. Ltd.

January
Managing Director

Chief End neer


B.S.E.I.D.C. Ltd, Patna


2

8 of 14

11 ...

		Supplementary BOQ for Constrution of Aryabna	Ι	1	, at with apar,	Patna 13
SL.	SOR No.	Tunite of Reins	Unit	Quantity	Rate (In digits)	Rate (In Words)
30	24.2.1.	Boring/drilling bore well of required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/ bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer -in-charge, beyond 90 metre & upto 150 metre depth below ground level 300 mm dia	Mtr.	70.00	434.80	Rupees Four Hundred Thirty Four and Eighty Paisas Only
31	24.8	Gravel packing in tubewell construction in accordance with IS: 4097,including providing gravel fine/ medium/ coarse, in required grading & sizes as per actual requirement, all complete as per direction of Engineer-incharge.	cum	45.50	1,011.40	Rupees One Thousand Eleven and Forty Paisas Only
32	and the second	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -in-charge. 100 mm nominal size dia	Mtr.	420.00	457.90	Rupees Four Hundred Fifty Seven and Ninety Paisas Only
33	24.3.4	Supplying, assembling, lowering and fixing in vertical position in bore well, unplasticized PVC medium well casing (CM) pipe of required dia, conforming to IS: 12818, including required hire and labour charges, fittings & accessories etc. all complete, for all depths, as per direction of Engineer -incharge. 50 mm nominal size dia	Mtr.	182.00	190.10	Rupees One Hundred Ninety and Ten Paisas Only
34	24.4.4	Supplying, assembling, lowering and fixing in vertical position in bore well unplasticized PVC medium well screen (RMS) pipes with ribs, conforming	Mtr.	98.00	310.00	Rupees Three Hundred Ten Only





..... ...

	T	Toppiementary BOQ for Constrution of Aryanna	T	wiedge Offiversi	ry at Miniapui,	Patna 14
SL.	SOR No.	rame of hema	Unit	Quantity	Rate (In digits)	Rate (In Words)
35	24,13.1	Providing and fixing suitable size threaded mild steel cap or spot welded plate to the top of bore well housing/ casing pipe, removable as per equirement, all complete for borewell of 100 mm dia	Each	7.00	171.90	Rupees One Hundred Seventy One and Ninety Paisas Only
36	24.14.1	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tubewell as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 100 mm clamp	Each	7.00	991,20	Rupees Nine Hundred Ninety One and Twenty Paisas Only
37	24.15.1	Providing and fixing Bail plug/ Bottom plug of required dia to the bottom of pipe assembly of tubewell as per IS:2800 (part I)	Each	7.00	212.20	Rupees Two Hundred Twelve and Twenty Paisas Only
38	24.12	Development of tube well in accordance with IS: 2800 (part I) and IS: 11189, to establish maximum rate of usable water yield without sand content (beyond permissible limit), with required capacity air compressor, running the compressor for required time till well is fully develo ped, measuring yield of well by "V" notch method or any other approved method, measuring static level & draw down etc. by step draw down method, collecting water samples & getting tested in approved laboratory, i/c disinfection of tubewell, all omplete, including hire & labour charges of air compressor, tools & accessories etc., all as per requirement and direction of Engineer-in-charge		168.00	646,00	Rupees Six Hundred Forty Six Only
39		Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete: 600 mm dia. R.C.C. pipe	Mtr.	160.00	1,358.00	Rupees One Thousand Three Hundred Fifty Eight Only
40	DSR 1.14	Wiring for circuit / submain wiring alongwith earth wire with the following sizes of PVC insulated, copper conductor single core cable in surface/ recessed medium class PVC conduit as required.				·
	1.14.10	4 x 16 sq.mm. + 2 x 16 sq.mm. Earth wire	М	2,063.63	891.83	Rupees Eight Hundred Ninety One and Eighty Three Paisas Only

For Dipanshu Promoter and Builder Pvt. Ltd.

Managing Director

Chief Eng neer
3.S.E.I.D.C. Ltd, Patna

SL.	SOR No.	Name of items	Unit	Quantity	Rate (in digits)	Rate (In Words)
41	DSR 2.20	Supplying and fixing 30 amps, 415 volts, TPN industrial type, socket outlet, with 4 pole and earth, metal enclosed plug top alongwith 30 amps "C" curve, TPMCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required	Each	3.00	2,497.73	Rupees Two Thousand Four Hundred Ninety Seven and Seventy Three Paisas Only
42	11.21.1 .1	Providing and fixing 10 mm thick acid and / or alkali resistant tiles of approved make and colour using acid and / or alkali resisting mortar bedding, and joints filled with acid and / or alkali resisting cement as per IS: 4457, complete as per the direction of Engineer-in-Charge in flooring on a bed of 10 mm thick mortar 1:4 (1 acid proof cement: 4 coarse sand). Acid and alkali resistant tile.	Sqm	2,094.96	1,211.00	Rupees One Thousand Two Hundred Eleven Only
43	QR	Providing, fitting & fixing of 25 mm UPVC full Way valve do do all complete job as per direction of E/I.		106.00	421.26	Rupees Four Hundred Twenty One and Twenty
44	· QR	Providing, fitting & fixing of 32 mm UPVC valve do do all complete job as per direction of E/I.		45.00	601.80	Six Paisas Only Rupees Six Hundred One and Eighty Paisas Only
45	OR	Providing, fitting & fixing of 40 mm UPVC valve do do all complete job as per direction of E/I.		64,00	798.86	Rupees Seven Hundred Ninety Eight and Eighty Six Paisas Only
46		Providing, fitting & fixing of 50 mm UPVC valve do do all complete job as per direction of E/I.		51.00	1,221.30	Rupees One Thousand Two
47		Providing, fitting & fixing of 65 mm UPVC valve do do all complete job as per direction of E/I.	i	30.00	3,204.88	Rupees Three Thousand Two Hundred Four and Eighty Eight Paisas Only
48	Ì	Providing, fitting & fixing of 80 mm UPVC valve do do all complete job as per direction of E/I.	Each	5.00	5,449.24	Rupees Five Thousand Four Hundred Forty Nine and Twenty Four Paisas Only

For Dipanshu Promoter and Builder Pvt. Ltd.

Zaman Managing Director

Chief Eng neer
3.S.E.I.D.C. Ltd, Patna

Mailmein action que	1		T	1		10
SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)
49	QR	Providing, fitting & fixing of 100 mm UPVC valve do do all complete job as per direction of E/I.		4.00	10,445.36	Rupees Ten Thousand Four Hundred Forty Five and Thirty Six Paisas Only
50	QR	Providing, fitting & fixing of 25 mm UPVC Union do do all complete job as per direction of E/I.	Each	67.00	109.74	Rupees One Hundred Nine and Seventy Four Paisas Only
51	QR	Providing, fitting & fixing of 32 mm UPVC Union do do all complete job as per direction of E/I.		49.00	135.70	Rupees One Hundred Thirty Five and Seventy Paisas Only
52	QR	Providing, fitting & fixing of 40 mm UPVC Union do do all complete job as per direction of E/I.	Each	73.00	250.16	Rupees Two Hundred Fifty and Sixteen Paisa Only
53	QR	Providing, fitting & fixing of 50 mm UPVC Union do do all complete job as per direction of E/I.	Each	78.00	285.56	Rupees Two Hundred Eighty Five and Fifty Six Paisas Only
54	QR	Providing, fitting & fixing of 65 mm UPVC Union do do all complete job as per direction of E/I.	Each	38.00	1,003.00	Rupees One Thousand Three Only
55		Providing, fitting & fixing of 80 mm UPVC Union do do all complete job as per direction of E/I.	Each	6.00	1,371.16	Rupees One Thousand Three Hundred Seventy One and Sixteen
56	OR	Providing, fitting & fixing of 100 mm UPVC Union do do all complete job as per direction of E/I.	Each	8.00	2,062.64	Paisas Only Rupees Two Thousand Sixty Two and Sixty Four Paisas Only
57		Providing, fitting & fixing of 50 mm UPVC Non Return Valve do do all complete job as per direction of E/I.	Each	6.00	3,674.52	Rupees Three Thousand Six Hundred Seventy Four and Fifty
58	QR	Providing, fitting & fixing of 110 mm UPVC Cowl do do all complete job as per direction of E/I.	Each	111.00	60.18	Two Paisas Only Rupees Sixty and Eighteen Paisas Only
59		Providing, fitting & fixing of 100 mm G.I. Union do do all complete job as per direction of E/I.	Each	5.00	1,353.46	Rupees One Thousand Three Hundred Fifty Three and Forty

For Dipanshu Promoter and Builder Pvt. Ltd.

Chief Eng neer

3.S.E.I.D.C. Ltd, Patna

J

- 1	-9
1	7

	·					
SL.	SOR No.	Name of items	Unit	Quantity	Rate (in digits)	Rate (In Words)
60	QR	Providing, fitting & fixing of CP Bib Cock two in one do do all complete job as per direction of E/I.		353.00	1,110.38	Rupees One Thousand One Hundred Ten and Thirty Eight Paisas Only
61	QR	Providing, fitting & fixing of PVC 110 mm SWR P- Trap Valve do do all complete job as per direction of E/I.		929.00	484.98	Rupees Four Hundred Eighty Four and Ninety Eight Paisas Only
62	QR	Providing, fitting & fixing of PVC 75 mm SWR P- Trap Valve do do all complete job as per direction of E/I.		1,00	322.14	Rupees Three Hundred Twenty Two and Fourteen Paisas Only
63	QR	Supply , installation, testing & commissionong of suitable capacity of and type of submersible pump set (1HP) cabable to discharge 10000 litres of clean filtered water from a deep tubewell at oa total head of 30 meter complete with control panel , gate valve , 60 mtr. of neoprane cable etc. complete as required	Each	7.00	40,069.26	Rupees Forty Thousand Sixty Nine and Twenty Six Paisas Only
64	QK	Supplying, Installation, Testing & Commissioning of Refregent pipe 5/8 and ½ copper tube with nytral rubber tube insulated including 3 core 2.5 sqmm copper wire do do all complete job as per direction of E/I.	Mtr.	300,00	1,585.00	Rupees One Thousand Five Hundred Eighty Five Only
65	QR	Supplying of 1.5 Ton Split AC 3 star rated with eco friendly green refregent R410A gas. (Daikin/Carrier/Hitachi/Voltas) do do all complete job as per direction of E/I.	Each	20.00	57,950.00	Rupees Fifty Seven Thousand Nine Hundred Fifty Only
66	QR	Supplying of 2 Ton Split AC 3 star rated with eco friendly green refregent R410A gas. (Daikin/Carrier/Hitachi/Voltas) do do all complete job as per direction of E/I.	Each	82.00	64,920.00	Rupees Sixty Four Thousand Nine Hundred Twenty Only
67	QR	Installation, Testing & Commissioning of Split AC do do all complete job as per direction of F/I	Each	102.00	4,000.00	Rupees Four Thousand Only
68	QR	4KVA Wall mounted automatic voltage stabilizer with hi/low cut off timer of make V-Guard do do all complete job as per direction of E/I.	Each	20.00	3,935.00	Rupees Three Thousand Nine Hundred Thirty Five Only

For Dipansin Promose and Builder Pvt. Ltd.

Jamas Managing Director

Chief Eng neer
B.S.E.I.D.C. Ltd, Patna

.)

SL.	SOR No.	Name of items	Unit	Quantity	Rate (In digits)	Rate (In Words)	
		5KVA Wall mounted automatic voltage				Rupees Five	
69	QR	stabilizer with hi/low cut off timer of make	I HOON I X7 OO I	5,475.00	Thousand Four		
	V	V-Guard do do all complete job as per	Luch	02.00	3,473.00	Hundred Seventy	
		direction of E/I.	•	C.		Five Only	
		Supplying & fitting of Drain with PVC				Rupees Three	
70	QR	rigid including required fitting and support		750,00	398.00	Hundred Ninety	
		do do all complete job as per direction of		· 12/2****	and the second	Eight Only	
		E/I. Supplying & fitting of powder coated iron	· ·			Rupees One	
		structure for placement of outdoor unit do				Thousand Four	
71	QR	do all complete job as per direction of E/I.	Each 1	102.00	1,475.00	Hundred Seventy	
		do an complete job as per uncerton of E/1.	M-1-		a de la companya del companya de la companya del companya de la co	Five Only	
· · · · · · · · · · · · · · · · · · ·						53,834,768.78	
penanouneous	Say Rs. 53,834,769.00						
	Rupees Five Crores Thirty Eight Lacs Thirty Four Thousand Seven Hundred Sixty Nine Only						

For Dipanshu Promoter and Builder Pvt. Ltd.

Managing Director

